

**Town of Monkton — Highway Department**  
**Church Road Work Project — 2026**

**Work zone:** Intersection of Bristol Road/Church Road to the intersection of Mountain Road/Church Road, .5 miles in length, not including the large culvert wetland area.

**Work Deadline:** Completed by October 1, 2026.

**Work Description:**

- **Tree Removal, to be completed by the Monkton Highway Department before contracted Work begins**
- Stump Removal by contractor.
- **Brush clearing to be completed by Monkton Highway Department, prior to contracted work commencing.**
- Ditching and erosion control on both the eastbound and westbound shoulders of Church Road, which is approximately .5 miles in length. Excess fill will be transported to local homeowners.
- Culvert replacements and additions
- Roadway rebuilding (using the full 25-foot traveled way as needed)
- 18-inch driveway culverts **to be provided by the Town of Monkton.**
- Driveway culverts to be installed by contractors for the following properties on Church Road: House number(s) 463, 435, 367, 366, 347, 295, 157, 123, 134. Also utilizing 4–6-inch erosion stone on both sides of the culverts once installed. **Stone will be provided by the Monkton Highway Department.**
- 4–6-inch erosion stone placed in the ditches along the inclines in the area of the bridge to allow for water to run off the road.
- Near the intersection of Church Road and Mountain Road, ditches will connect with pre-existing ditches alongside Mountain Road to allow for water to flow.

**Equipment on site:**

- Excavator Allowing for one (1) lane of travel to be open at all times
- Tandem-axle dump truck(s)
- John Deere 672P motor grader, work to be completed by the Town of Monkton highway department and the conclusion of contracted work.
- Brush Chipper by Monkton Highway Department.
- Full sign package (Road Work, Be Prepared to Stop, Flagger signs)

**Traffic and safety:**

- Flaggers may be present at times.
- Please “Slow Down and Move Over” when possible. Do not pass if you are unsure what’s ahead of the work zone.
- Expect delays and plan accordingly.

**Requested information from Contractor:**

- Provide proof of insurance prior to work commencing.
- Hourly Rate and size of excavator utilized
- Hourly Rate for dump truck
- Hourly Rate for labor
- Lump sum bid for traffic and safety
- Estimated time to complete work.

**BID DEADLINE: July 9<sup>th</sup>, 2026 at 12pm**

For Questions and To Submit a Bid Estimate, please email:

Joe Szarejko, Highway Department Liaison

**Email: [jszarejko@monktonvt.com](mailto:jszarejko@monktonvt.com)**